

ANNEXURE-4

Details of DG Set at the sites of PMRP

Sr. No.	Reach	Station Name	DG Capacity (KVA)	DG Output Voltage	DG with AMF Panel (Yes/No)
1	Reach-1	PCMC	250	3 Ph, 415 V	Yes
2		Sant Tukaram Nagar	250	3 Ph, 415 V	Yes
3		Bhosari	250	3 Ph, 415 V	Yes
4		Kasarwadi	250	3 Ph, 415 V	Yes
5		Phugewadi	250	3 Ph, 415 V	Yes
6		Range Hill Depot	625	3 Ph, 415 V	Yes
7	Reach-2	Vanaz	250	3 Ph, 415 V	Yes
8		Anand Nagar	250	3 Ph, 415 V	Yes
9		Ideal Colony	250	3 Ph, 415 V	Yes
10		Nal Stop	250	3 Ph, 415 V	Yes
11		Garware College	250	3 Ph, 415 V	Yes
12		Hill View Park Car Depot	625	3 Ph, 415 V	Yes

Note: DG synchronisation with solar feeder is in the scope of bidder. However, DG manufacturer is providing the AMF Panel along with synchroniser and associated PLC to automatically switch on DG in the event of power failure (Normal supply). Bidder has to interface with DG manufacturer/E&M Contractor for synchronisation.